



## Enhanced commissioning

EAC2 | Possible 5 points

### Intent

To verify and ensure that the tenant space is designed, constructed and calibrated to operate as intended.

### Requirements

Implement, or have a contract in place to implement, the following additional commissioning process activities in addition to the requirements of EA Prerequisite 1: Fundamental Commissioning of Building Energy Systems:

- Prior to the start of the construction documents phase, designate an independent commissioning authority (CxA) to lead, review and oversee the completion of all commissioning process activities.
- The CxA must have documented commissioning authority experience in at least 2 building projects.
- The individual serving as the CxA:
  - Must be independent of the work of design and construction;
  - Must not be an employee of the design firm, though he or she may be contracted through them;
  - Must not be an employee of, or contracted through, a contractor or construction manager holding construction contracts;
  - May be a qualified employee or consultant of the owner.
- The CxA must report results, findings and recommendations directly to the owner.
- The CxA must conduct, at a minimum, 1 commissioning design review of the owner's project requirements, basis of design and design documents prior to the mid-construction documents phase and must back-check the review comments in the subsequent design submission.
- The CxA must review contractor submittals applicable to systems being commissioned for compliance with the owner's project requirements and basis of design. This review must be concurrent with the reviews of the architect or engineer of record and submitted to the design team and the owner.
- The CxA or other project team members must develop a systems manual that gives future operating staff the information needed to understand and optimally operate the project's commissioned systems.
- The CxA or other project team members must verify that the requirements for training operating personnel and building occupants have been completed.
- The CxA must be involved in reviewing the operation of the tenant space with operations and maintenance (O&M) staff and occupants within 8 to 10 months after substantial completion. A plan for resolving outstanding commissioning-related issues must be included.

#### **Credit substitution available**

You may use the LEED v4 version of this credit on v2009 projects. For more information [check out this article](#).