USGBC.org - Scheduled Maintenance May 06th - May 07th
USGBC.org will be offline from **May 06th Friday 9:00pm EST - May 07th Saturday 12:00pm EST**.
Email us or call 1-800-795-1747 for assistance. Thanks for your patience.

LEED ID+C: Commercial Interiors | v3 - LEED 2009

Thermal comfort - verification

EQc7.2 | Possible 1 point

Glossary

Intent

To provide for the assessment of occupant thermal comfort over time.

Requirements

Achieve IEQ Credit 7.1: Thermal Comfort – Design

Provide a permanent monitoring system and process for corrective action to ensure that building performance meets the desired comfort criteria as determined by IEQ Credit 7.1: Thermal Comfort—Design.

Agree to conduct a thermal comfort survey of tenant space occupants within 6 to 18 months after occupancy. This survey should collect anonymous responses about thermal comfort in the tenant space including an assessment of overall satisfaction with thermal performance and identification of thermal comfort problems. Agree to develop a plan for corrective action if the survey results indicate that more than 20% of occupants are dissatisfied with thermal comfort in the tenant space This plan should include measurement of relevant environmental variables in problem areas in accordance with the standard used for design in IEQ Credit 7.1: Thermal Comfort—Design.