



| v2 - LEED 2.0

Construction, demolition and renovation waste management

MRc1.1 | Possible 1 point

Glossary

Intent

Divert construction, demolition and land-clearing debris from landfill and incineration disposal. Redirect recyclable recovered resources back to the manufacturing process. Redirect reusable materials to appropriate sites.

Requirements

Develop and implement a Waste Management Policy covering any future building retrofit, renovation or modification on the site. Quantify diversions of construction, demolition and land-clearing debris from landfill and incineration disposal by weight or volume.

- MR Credit 1.1: Divert at least 50% of construction, demolition and land-clearing waste from landfill and incineration disposal. (1 point)
- MR Credit 1.2: Divert at least 75% of construction, demolition and land-clearing waste from landfill and incineration disposal. (1 additional point)