



| v2 - Schools 2007

## Construction IAQ management plan: during construction

EQc3.1 | Possible 1 point

Glossary

### Intent

Reduce indoor air quality problems resulting from the construction/renovation process in order to help sustain the comfort and well-being of construction workers and building occupants.

### Requirements

Develop and implement an Indoor Air Quality (IAQ) Management Plan for the construction and pre-occupancy phases of the building as follows:

- During construction meet or exceed the recommended Control Measures of the Sheet Metal and Air Conditioning National Contractors Association (SMACNA) IAQ Guidelines for Occupied Buildings under Construction, Second Edition - November 2007, Chapter 3.
- Protect stored on-site or installed absorptive materials from moisture damage.
- If permanently installed air handlers are used during construction, filtration media with a Minimum Efficiency Reporting Value (MERV) of 8 shall be used at each return air grille, as determined by ASHRAE 52.2-1999. Replace all filtration media immediately prior to occupancy.
- Prohibit smoking inside the building and within 25 feet of building entrances once the building is enclosed.