| v2 - LEED 2.1

Fundamental building systems commissioning

EAp1 | Required

Glossary

Intent

Verify and ensure that fundamental building elements and systems are designed, installed and calibrated to operate as intended.

Requirements

Implement or have a contract in place to implement the following fundamental best practice commissioning procedures.

- Engage a commissioning team that does not include individuals directly responsible for project design or construction management.
- Review the design intent and the basis of design documentation.
- Incorporate commissioning requirements into the construction documents.
- Develop and utilize a commissioning plan.
- Verify installation, functional performance, training and operation and maintenance documentation.
- Complete a commissioning report.

Address
2101 L Street NW
Suite 500
Washington, DC 20037

Within the United States:
1-800-795-1747

Outside the United States:
1-202-742-3792

© 2012-2015 U.S. Green Building Council