



LEED ID+C: Retail | v4 - LEED v4

Construction indoor air quality management plan

Possible 1 point

Glossary

Intent

To promote the well-being of construction workers and building occupants by minimizing indoor air quality problems associated with construction and renovation.

Requirements

Develop and implement an indoor air quality (IAQ) management plan for the construction and preoccupancy phases of the building. The plan must address all of the following.

During construction, meet or exceed all applicable recommended control measures of the Sheet Metal and Air Conditioning National Contractors Association (SMACNA) IAQ Guidelines for Occupied Buildings under Construction, 2nd edition, 2007, ANSI/SMACNA 008-2008, Chapter 3.

Protect absorptive materials stored on-site and installed from moisture damage.

Do not operate permanently installed air-handling equipment during construction unless filtration media with a minimum efficiency reporting value (MERV) of 8, as determined by ASHRAE 52.2-2007, with errata (or equivalent filtration media class of F5 or higher, as defined by CEN Standard EN 779-2002, Particulate Air Filters for General Ventilation, Determination of the Filtration Performance), are installed at each return air grille and return or transfer duct inlet opening such that there is no bypass around the filtration media. Immediately before occupancy, replace all filtration media with the final design filtration media, installed in accordance with the manufacturer's recommendations.

Prohibit the use of tobacco products inside the building and within 25 feet (8 meters) of the building entrance during construction.